

Combined Risk Assessment: Installation and Mechanical Movement of a Mega Box Container

Issued: 1st January 2026 . Reference: megabox-movement

Installation

Procedure Being Assessed

The installation of a mega box container.

Required Training

Full knowledge of the assembly and disassembly of a mega box.
In-house manual lifting techniques.

Risks

To the General Public

The public getting knocked, by being in the way.

To You (Worker)

Cutting your hands on the mega box parts.
Hurting yourself by lifting wrong.

To Work Colleagues

Work colleague may get hit by you working.
Lack of communication may cause accidents.

Other Risks

Walking backwards while transporting parts of the mega box with a colleague.

Risk Reduction Measures

For the General Public

Create a safe working area during the build up/down of a mega box using visual aids or a look out.
All staff should wear high-visibility clothing.

For You (Worker)

Gloves should always be worn when lifting or working with mega box.
Never lift anything heavier than you can comfortably lift. Find help or use mechanical aid.

For Work Colleagues

Always make everyone aware what has to be done and how it will be tackled. Discuss on-site risk assessments to make everyone aware of the dangers and how they can be reduced.

For Other Risks

Always plan your route, and have a colleague direct you over tricky surfaces.

Combined Risk Assessment: Installation and Mechanical Movement of a Mega Box Container

Mechanical Movement

Procedure Being Assessed

The transportation of a mega box container using mechanical aid.

Required Training

In-house training certificate of the mechanical aid being used.
Knowledge of what is being transported.

Risks

To the General Public

The public getting knocked, by being in the way.

To You (Worker)

(None identified.)

To Work Colleagues

Work colleague may get hit by you working.
Lack of communication may cause accidents.

Other Risks

Reduced visibility by the load may make transporting dangerous.

Risk Reduction Measures

For the General Public

Always use a banksman when working in congested areas to keep the public clear of all movements made.
All visible aids on the mechanical aid will be in good working order and used to the full effect.
Always make sure extended legs are used when using a forklift truck to transport the mega box. This increases load security.
Carry the load as close to the ground as possible.

For You (Worker)

(None identified.)

For Work Colleagues

Always make everyone aware what has to be done and how it will be tackled. Discuss on-site risk assessments to make everyone aware of the dangers and how they can be reduced.

For Other Risks

Always plan your route, and have a colleague direct you over tricky surfaces.

Has the Risk Been Reduced Enough?

Yes, provided all mitigation measures are followed consistently and workers remain vigilant.

Combined Risk Assessment: Installation and Mechanical Movement of a Mega Box Container

Approved on behalf of Fence Hire (Southern) Ltd:

SD Kinnear

Scott Kinnear

Director . Issued: 1st January 2026